

秋田自動車道
峠山トンネル工事用仮橋設置工事

数 量 明 細 表

令和8年4月

東日本高速道路株式会社 東北支社
横手工事事務所

数量明細表 (1/4)

名称	1	2	3	4	5	6	7	8	9	10	11	12
	2-(2)	2-(4)	2-(5)		2-(6)	4-(3)	4-(4)	4-(19)	5-(2)		18-(3)	
	道路掘削	捨土掘削	盛土工		構造物掘削	種散布工	種吹付工	ふとんかご工	用排水管		簡易舗装工	
	土砂	土砂(表土)	盛土工 A1	盛土工 A2	普通部	種散布工	種吹付 A (人工基材)	2. 0m・0. 5m・ 1. 2m・13cm	P(Po-B) ・Φ0. 20(S d-B)A	P(Po-B) ・Φ0. 80(S d-B)A	切込碎石 路盤工 (t=20cm)	再生碎石 路盤工 (t=20cm)
	m ³	m ³	m ³	m ³	m ³	m ²	m ²	枚	m	m	m ²	m ²
【南本内地区:仮橋】												
【小荒沢地区:仮橋】												
A												
B												
C												
【小荒沢地区:土工部】												
①	219.8	1,083.2	1,080.3			537.8	219.0		98.6		3,047.6	
②	34.6	162.1		365.5		81.2		58.0	112.9			629.1
③	3.0			22.1	73.9				7.2	16.8		80.0
雑工												
合計	257.4	1,245.3	1,080.3	387.6	73.9	619.0	219.0	58.0	218.7	16.8	3,047.6	709.1
契約数量	257	1,245	1,080	388	74	619	219	58	219	17	3,048	709

数量明細表 (2/4)

名称	13	14	15	16	17	18	19	20	21	22	23	24
	18-(3)	19-(2)	特-(1)						特-(2)			
	簡易舗装工	交通保安要員	工事用仮橋						工事用仮橋			
	加熱 アスファルト 表層工 (t=5cm)	交通誘導 警備員B	上部工 南本内川	上部工 小荒沢地区 仮橋A(1)	上部工 小荒沢地区 仮橋A(2)	上部工 小荒沢地区 仮橋A(3)	上部工 小荒沢地区 仮橋B	上部工 小荒沢地区 仮橋C	下部工 南本内川(1)	下部工 南本内川(2) -①	下部工 南本内川(2) -②	下部工 南本内川(2) -③
	m ²	人・日	t	t	t	t・月	t	t	t	t	t	t・月
【南本内地区:仮橋】												
			171.747						121.953	44.513	17.100	347.1
【小荒沢地区:仮橋】												
A				542.268	661.984	7078.3						
B							85.588					
C								37.776				
【小荒沢地区:土工部】												
①												
②	629.1											
③	80.0											
雑工												
		1103.0										
合計												
	709.1	1,103.0	171.747	542.268	661.984	7,078.3	85.588	37.776	121.953	44.513	17.100	347.1
契約数量												
	709	1,103	171.75	542.27	661.98	7,078	85.59	37.78	121.95	44.51	17.10	347

数量明細表 (3/4)

名称	25	26	27	28	29	30	31	32	33	34	35	36
	特-(2)				特-(3)						特-(4)	
	工事用仮橋				工事用仮橋						防護柵撤去	
	下部工 南本内川(3) -①	下部工 南本内川(3) -②	下部工 南本内川(3) -③	下部工 小荒沢地区 仮橋A	基礎工 南本内川(1)	基礎工 南本内川(2)	基礎工 南本内川(3)	基礎工 小荒沢地区 仮橋A	基礎工 小荒沢地区 仮橋B	基礎工 小荒沢地区 仮橋C	防護柵撤去A	防護柵撤去B
	t	t	t・月	t	本	本	本	本	本	m	m	m
【南本内地区:仮橋】												
	127.957	34.200	694.2		62.0	4.0	12.0					
【小荒沢地区:仮橋】												
A				424.218				156.0				
B									16.0			
C										67.8		
【小荒沢地区:土工部】												
①												
②												
③												
雑工												
											128.3	12.2
合計	127.957	34.200	694.2	424.218	62.0	4.0	12.0	156.0	16.0	67.8	128.3	12.2
契約数量	127.96	34.20	694	424.22	62	4	12	156	16	68	128	12

数量明細表 (4/4)

名称	37	38	39	40	41							
	特-(5)	特-(6)	特-(7)									
	仮設防護柵工	既設水路保護工	除雪工									
	仮設防護柵	敷鉄板敷設	A	B	C							
	m	枚	台・h	台・h	人・h							
【南本内地区:仮橋】												
【小荒沢地区:仮橋】												
A												
B												
C												
【小荒沢地区:土工部】												
①												
②												
③												
雑工												
	108.0	9.0	264.0	264.0	264.0							
合計												
	108.0	9.0	264.0	264.0	264.0							
契約数量												
	108	9	264	264	264							