

道 東 自 動 車 道
本 流 鷗 川 第 一 橋 (鋼 上 部 工) 工 事

数 量 明 細 表 (契 約 項 目)
(参 考)

令 和 8 年 1 0 月

東 日 本 高 速 道 路 株 式 会 社 北 海 道 支 社
帯 広 工 事 事 務 所

数量明細表（1／6）

番 号	名称又は測点	番号	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
		項目番号	8－（１）				8－（２）		8－（３）				9－（２）	10－（４）	10－（５）				
		単価表の	コンクリート				型わく		鉄筋				P C鋼材引張	鋼構造物の 輸送	鋼構造物の架設				
		項目	A 1－1	A 1－3	A 1－4	P 2－2	A	C	A	A（E）	B	C（E）	P C鋼より 線（1 S 2 8．6）S	鋼橋の輸送	鋼橋の架設 （Ⅰ）	鋼橋の架設 （Ⅱ）	鋼橋の架設 （Ⅲ）	鋼橋の架設 （Ⅳ）	鋼橋の架設 （Ⅴ）
		単位	m ³	m ³	m ³	m ³	m ²	m ²	t	t	t	t	kg	t	t	t	t	t	t
1																			
	橋梁上部工		190.5	0.0	434.4	2,002.2	8,898.1	0.0	472.179	161.894	0.000	0.000	61,128.0	1,095.421	356.783	139.054	154.710	237.001	107.676
	本流鷓川第一橋		52.7		86.5	510.8	2,113.0		111.942	40.970			17,128.0	356.783	356.783				
	本流鷓川第二橋		33.0		66.2	329.8	1,402.4		84.371	24.599			10,145.0	139.054		139.054			
	本流鷓川第三橋		32.9		65.9	373.1	1,467.1		91.486	25.763			10,935.0	154.710			154.710		
	本流鷓川第四橋		34.7		83.1	426.0	1,779.1		110.589	31.695			13,242.0	237.001				237.001	
	占冠PAランプ橋		17.2		64.5	179.1	986.4		39.508	17.843			4,545.0	107.676					107.676
2																			
	橋梁下部工		0	173.1	60.8	0	0	802.7	2.876	13.260	1.028	0.144	0	0	0	0	0	0	0
	本流鷓川第一橋			11.4	11.7			107.3	0.474	0.628									
	本流鷓川第二橋			8.8	10.5			93.0	0.420	0.572									
	本流鷓川第三橋			9.4	9.0			85.0	0.357	0.505									
	本流鷓川第四橋			9.0	10.3			93.0	0.413	0.569									
	占冠PAランプ橋			131.1	10.7			352.3	0.774	10.345	1.028	0.144							
	占冠PAアクセス路橋			3.4	8.6			72.1	0.438	0.641									
	合 計		190.5	173.1	495.2	2,002.2	8,898.1	802.7	475.055	175.154	1.028	0.144	61,128.0	1,095.421	356.783	139.054	154.710	237.001	107.676

数量明細表（2／6）

番 号	名称又は測点	番号	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34
		項目番号	10 - (5)							11 - (1)									
		単価表の	鋼構造物の架設							支 承									
		項目	鋼橋の架設 (Ⅵ)	高力ボルト 本締工	鋼橋の 現場溶接工 (Ⅰ)	鋼橋の 現場溶接工 (Ⅱ)	鋼橋の 現場溶接工 (Ⅲ)	鋼橋の 現場溶接工 (Ⅳ)	鋼橋の 現場溶接工 (Ⅴ)	鋼橋の 現場溶接工 (Ⅵ)	E - 1	E - 2	E - 3	E - 4	E - 5	E - 6	E - 7	E - 8	E - 9
		単位	t	t	m	m	m	m	m	m	箇所	箇所	箇所	箇所	箇所	箇所	箇所	箇所	箇所
1																			
	橋梁上部工		100.197	7.927	129.7	64.5	64.5	87.4	55.7	48.8	3	3	3	4	2	4	2	4	2
	本流鷓川第一橋			3.072	129.7						3	3	3						
	本流鷓川第二橋			0.932		64.5								4	2				
	本流鷓川第三橋			0.886			64.5									4	2		
	本流鷓川第四橋			1.322				87.4										4	2
	占冠PAランプ橋			0.807					55.7										
2	占冠PAアクセス路橋		100.197	0.908						48.8									
	橋梁下部工		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	本流鷓川第一橋																		
	本流鷓川第二橋																		
	本流鷓川第三橋																		
	本流鷓川第四橋																		
	占冠PAランプ橋																		
	占冠PAアクセス路橋																		
	合 計		100.197	7.927	129.7	64.5	64.5	87.4	55.7	48.8	3	3	3	4	2	4	2	4	2

数量明細表（3／6）

番 号	名称又は測点	番号	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51
		項目番号	11 - (1)					11 - (2)	11 - (3)		11 - (5)	11 - (6)	11 - (8)						
		単価表の 項目	支 承					伸縮装置	排水装置		橋名板	橋歴板	落橋防止構造						
			E－１０	E－１１	E－１２	E－１３	E－１４	E (S=116 mm)	排水ます A １	排水ます A ２			A １	A ２	A ３	A ４	A ５	A ６	A ７
		単位	箇所	箇所	箇所	箇所	箇所	m	箇所	箇所	箇所	箇所	kg	kg	kg	kg	kg	kg	kg
1																			
	橋梁上部工		4	2	2	2	2	16.0	55	35	6	6	262.8	365.2	230.8	230.8	230.8	230.8	260.8
	本流鷓川第一橋								17	17	1	1	262.8	365.2					
	本流鷓川第二橋								7	7	1	1			230.8	230.8			
	本流鷓川第三橋								2	2	1	1					230.8	230.8	
	本流鷓川第四橋								3	3	1	1							260.8
	占冠PAランプ橋		4	2					6	6	1	1							
	占冠PAアクセス路橋				2	2	2	16.0	20		1	1							
2																			
	橋梁下部工		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	本流鷓川第一橋																		
	本流鷓川第二橋																		
	本流鷓川第三橋																		
	本流鷓川第四橋																		
	占冠PAランプ橋																		
	占冠PAアクセス路橋																		
	合 計		4	2	2	2	2	16.0	55	35	6	6	262.8	365.2	230.8	230.8	230.8	230.8	260.8

数量明細表（4／6）

番 号	名称又は測点	番号	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68
		項目番号	11 - (8)			17 - (31)	17 - (32)	特 - (1)	10 - (2)										
		単価表の 項目	落橋防止構造			はく落防止 対策工	表面保護工	率計上工事 に関する事 項	鋼構造物の製作										
			A 8	A 9	A 1 0	A	コンクリー ト表面被覆 工	A	製作材料費 （鋼板） A	製作材料費 （鋼板） B	製作材料費 （鋼板） C	製作材料費 （形鋼） A	製作材料費 （スタッド ジベル）	大型部材の 製作 （Ⅰ）	大型部材の 製作 （Ⅱ）	大型部材の 製作 （Ⅲ）	大型部材の 製作 （Ⅳ）	大型部材の 製作 （Ⅴ）	大型部材の 製作 （Ⅵ）
		単位	kg	kg	kg	m ²	m ²	式	t	t	t	t	t	個	個	個	個	個	個
1																			
	橋梁上部工		260.8	124.0	124.0	147.2	393.7	1	81.181	852.833	93.792	55.179	19.277	117	63	63	75	63	57
	本流鷓川第一橋					0.0	99.4		29.207	262.462	40.128	20.818	5.346	117					
	本流鷓川第二橋					0.0	59.7		10.098	110.892	13.212	6.357	2.798		63				
	本流鷓川第三橋					0.0	62.1		12.071	117.258	14.848	7.692	3.156			63			
	本流鷓川第四橋		260.8			147.2	70.1		13.611	182.930	25.604	11.592	3.743				75		
	占冠PAランプ橋			124.0	124.0	0.0	33.2		8.071	93.778		3.664	2.436					63	
	占冠PAアクセス路橋						69.2		8.123	85.513		5.056	1.798						57
2																			
	橋梁下部工		0	0	0	0	763.6	1	0	0	0	0	0	0	0	0	0	0	0
	本流鷓川第一橋						172.9												
	本流鷓川第二橋						136.0												
	本流鷓川第三橋						142.0												
	本流鷓川第四橋						137.9												
	占冠PAランプ橋						81.8												
	占冠PAアクセス路橋						93.0												
	合 計		260.8	124.0	124.0	147.2	1,157.3	1	81.181	852.833	93.792	55.179	19.277	117	63	63	75	63	57

数量明細表（5／6）

番 号	名称又は測点	番号	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85
		項目番号	10 - (2)													10 - (3)	11 - (2)	10 - (1)	
		単価表の	鋼構造物の製作													鋼構造物の 防錆	伸縮装置	鋼構造物の 詳細設計	
		項目	小型部材の 製作 (Ⅰ)	小型部材の 製作 (Ⅱ)	小型部材の 製作 (Ⅲ)	小型部材の 製作 (Ⅳ)	小型部材の 製作 (Ⅴ)	小型部材の 製作 (Ⅵ)	中間横桁部 材の製作 (Ⅰ)	中間横桁部 材の製作 (Ⅱ)	中間横桁部 材の製作 (Ⅲ)	中間横桁部 材の製作 (Ⅳ)	中間横桁部 材の製作 (Ⅴ)	中間横桁部 材の製作 (Ⅵ)	T継手溶接 工	鋼構造物の 塗装 C－5	A	鋼構造物の 詳細設計 (Ⅰ)	鋼構造物の 詳細設計 (Ⅱ)
		単位	個	個	個	個	個	個	個	個	個	個	個	個	m	m ²	kg	式	式
1																			
	橋梁上部工		1,362	610	607	802	591	519	24	8	8	12	8	9	5,371.6	12,009.1	80,374.0	1	1
	本流鷓川第一橋		1,362						24						1,467.9	3,597.6	20,985.0	1	
	本流鷓川第二橋			610						8					767.6	1,658.4	15,691.0		1
	本流鷓川第三橋				607						8				767.2	1,720.5	17,316.0		
	本流鷓川第四橋					802						12			955.8	2,346.0	16,774.0		
	占冠PAランプ橋						591						8		725.1	1,367.4	9,608.0		
	占冠PAアクセス路橋							519						9	688.0	1,319.2			
2																			
	橋梁下部工		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	本流鷓川第一橋																		
	本流鷓川第二橋																		
	本流鷓川第三橋																		
	本流鷓川第四橋																		
	占冠PAランプ橋																		
	占冠PAアクセス路橋																		
	合 計		1,362	610	607	802	591	519	24	8	8	12	8	9	5,371.6	12,009.1	80,374	1	1

数量明細表 (6/6)

[illegible]